DOPAS DOPAS **Training Workshop 2015** D1 1.3.2 **Scoping the DOMPLU experiment** at Äspö HRL Pär Grahm, SKB 14 September 2015 The research leading to these results has received funding from the European Union's European Atomic Energy Community's (Euratom) Seventh Framework Programme FP7/2007-2013, under Grant Agreement No. 323273 for the DOPAS project. nagra B+TECH Správa úložišť radioaktivních odpadů POSIVA Radioactive Waste 🛃 Management Galson Sciences Ltd ANDRA

Outline of this lecture

1. Information about the DOMPLU experiment

- Objectives (partially based on requirements)
- Experimental layout
- Photos from installation
- Example of results and conclusions
- 2. Scoping a technical development project
 - Useful tool: Work Breakdown Structure (WBS)
 - Group work: Create a WBS for the DOMPLU full scale experiment



Part 1 – Information about DOMPLU



The DOMPLU experiment

• DOMPLU is a full-scale test of the plug system in realistic conditions at Äspö HRL (-450 m) with 4 MPa water pressure in the deposition tunnel.



Acknowledgement

- DOMPLU is conducted as a joint project between SKB and Posiva. Correspondingly, SKB takes part of Posiva's plug project POPLU in ONKALO.
- Both DOMPLU and POPLU are part of the Full-Scale Demonstration Of Plugs And Seals (DOPAS) project.

The research leading to these results has recieved funding from the European Union's European Atomic Energy Community's (Euratom) Seventh Framework Programme FP7/2007-2013 under grant agreement no 323273, the DOPAS project. More info can be found at the Dopas website: www.posiva.fi/dopas





DOMPLU objectives (major)

- Construction of a dome plug system according to design specifications (SKB TR-10-16) in the license application.
- Improve the plug design and verify quality control of installation and commissioning in full-scale.
- Control water tightness of the plug. Recent analyses allow a maximum leakage of <0.1 l/min past the plug. (SKB TR-14-22, in preparation)



Preparations before full-scale

- Laboratory tests of plug component materials:
 - Filter/Drainage (gravel in different fractions, geotextiles, LECA)
 - Bentonite Seal, MX-80 blocks and pellets
 - Low-pH Concrete, recipe B200 (SKB R-09-07)
- Analytical and Numerical calculations for design purposes and full-scale test predictions
 - Hydro-Mechanical modelling of Bentonite Seal Filter Backfill
 - Thermal and structural responses of the Concrete Dome
- Downscaled (1:10) tests of the plug system (6 trial cycles)
- Äspö HRL field-tests (slot excavation, contact grouting)
- Pilot borehole core characterisation and water injections



DOMPLU layout





56 sensors in the concrete dome Gap-width, deformation, strains and temperatures.

3 supplementary sensors in the leadthrough pipe and the drainpipes Pore pressures

48 sensors in the bentonite seal, filter and backfill Total and pore pressures, RH & temperatures, displacements.





Monitoring of leakage On-line scale

Slot excavation by wire sawing





- Symmetrical octagon design (16 cuts, \approx 8.8 m)
- Safety scaffold structure for workers protection



The excavated slot



• View of the excavated slot for casing of the concrete dome

• Model composed of laser scanning data



Installation 1 (3)

- 3 lead-through pipes for sensor cabling and water inlet pipes
 - Backfill blocks/pellets and LECA beams
 - Gravel filter, bentonite seal (MX-80 blocks/pellets) and concrete beams





Installation 2 (3)

- Grouting tubes (3 sections)
- Geotextile (2 layers)



- Concrete sensors
- Cooling system





Installation 3 (3)



- Formwork (by Doka)
- Casting (94 m³ B200)
 - Non-reinforced structure



• Chillers (redundant)

DOMPLU in operation



- On-line leakage measurements.
- Plastic sheet reduces effects of tunnel ventilation and evaporation.

- Monitoring have been carried out since March 2013.
- Full water pressure 4 MPa was reached in February 2014.
- Data freeze for the DOPAS project: September 30, 2014.

Water escapes







One significant water escape has been identified in this area (fracture B107), located about 14 meters in front of the pressure chamber

1. Cables

- 2. Rock fracture
- 3. Plug/Rock interface

Water inflow and leakage trends



September 30, 2014: The measured leakage past the plug (in weir) was 0.04 l/min at 4 MPa water pressure (this was about 11% of the inflow)

Conclusions (in selection)

- In general, plug construction was successful and workers safety aspects were handled in a good way. Learnings: Formwork can be redesigned, installations at tunnel ceiling can be improved.
- Initially, all sensors worked well. A few sensors failed during contact grouting and other sensors have failed due to water pressure increase.
- Sensors data correspond very well to predictive calculations.
- The plug is tighter than the rock!
- The leakage past the plug (collected in the weir) is well below 0.1 l/min and the trend is decreasing. Seal is not yet saturated.



DOMPLU coming work

- Technical reporting. DOPAS deliverable D4.3
- DOMPLU results will lead to a "light update" of the basic design of deposition tunnel plugs in the Spent Fuel Repository.
- Operation and monitoring of DOMPLU will continue at 4 MPa water pressure, at least until late 2016
- DOMPLU will be opened and retrieved in 2017. A final load test (close to the design load of 9 MPa) is a unique opportunity to verify the design of the concrete dome and the numerical models used.



DOMPLU publications

- <u>SKB P-13-37</u> System design of Dome plug. Creep properties at high stress levels of concrete for deposition tunnel plugs. (published)
- <u>SKB P-13-38</u> System design of Dome plug. Mechanical properties of rock-concrete interface (published)
- <u>SKB P-14-26</u> Experience of low-pH concrete mix B200. Material properties from laboratory tests and full-scale castings (in preparation)
- <u>SKB R-14-24</u> System design of Dome Plug. Experiences from wire sawing of a slot abutment for the KBS-3V deposition tunnel plug (in preparation)
- <u>SKB R-14-25</u> System design of Dome Plug. Preparatory modelling and tests of the sealing and draining components (in preparation)
- <u>KTH TRITA-BKN147</u> Instrumentation and Evaluation of the Concrete Dome Plug.
- <u>SKB TR-14-23</u> System design and full-scale testing of the Dome Plug for KBS-3V deposition tunnels. Main report (in preparation)

Part 2 – Scope Management





Determining the scope

- An essential part of the project planning is to define a scope statement.
- Correct and proper breakdown of the scope is essential for a successful project (i.e. to fulfil the project objectives and meet the Client's expectation on the deliveries).
- Subdivision of major project deliveries should be done in a <u>Work Breakdown Structure (WBS)</u>. *
 - * ISO 21500 Guidance on project management
 - ISO 10006 Guideline to Quality in project management
 - PMBOK Guide (Project Management Institute)



What is a WBS?

A hierarchically-structured grouping of project elements: •



- **Defines total** scope
- **Deliverable**oriented
- **Schematic**
- Id-No. on each work package
- Can be used for each project phase



Why use WBS?

- Advantages with a Work Breakdown Structure:
 - Gives a common understanding of what to do
 - Improves the accuracy of cost, time, and resource estimations
 - Gives a baseline for performance measurement and control
 - Facilitates clear assignment of responsibilities
- A good WBS makes it easier to keep control of the scope!
 - Regular follow-up of WBS work packages
 - Checkpoint for limitations
 - Any changes of scope to be approved by the Client.
 - Use project change forms!



How to create a WBS (some tips)

- Identification of work packages
 - Engage people with various background and competence (include specialists).
 - Brainstorm on blank paper. For instance, use Post-it notes and pen.
 - Use experiences and lessons learned from similar projects.
 - Arrange the work packages in a strategic and schematic way.
- Verification of scope
 - ✓ Summarise and discuss in the project team
 - ✓ Use a reference group for review and further input
 - ✓ Formal approval by the Client





Group work - WBS

- Create a WBS for the DOMPLU full scale experiment
- Focus on the project phase <u>Installation</u> (including monitoring)
- Use information in the previous presentation (DOMPLU layout, and photos from installation)

• Ask experts (if necessary ;)



Group work – WBS





Presentation of group work





Thank you for a great team work!



www.posiva.fi/en/dopas



The research leading to these results has received funding from the European Atomic Energy Community's (Euratom) Seventh Framework Programme FP7/2007-2013, under Grant Agreement No. 323273 for the DOPAS project.



Conditions for use of this training material

The training materials for the DOPAS Training Workshop 2015 have been produced partly with the European Commission's financial support. The materials can be downloaded from the DOPAS WP7 webpage and used in general freely without a permission for non-commercial purposes providing the source of the material and Commission support is referred to.

The figures and pictures in each presentation originate from the organisation that has produced the specific training material unless mentioned otherwise.

Some photos and materials in the presentations present prior knowledge (background information) of the consortium partners. This information is marked with © and requires a permission for all uses from the copyright owner.

Non-commercial use means that if this training material is used e.g. in education, training, or consulting no fee may be collected from using this material. For other uses, please contact the DOPAS project.

